



Haralson County School District

Work List

Notes: 1. All Work listed are Turn-Key (materials, labor & equipment). Please list all items as line items when pricing. The following work list items are provided by the Owner for convenience and are not guaranteed to be accurate. Drawings are provided for clarification.

Contractor must comply with Davis-Bacon Wages Act

Haralson County High School
1655 Hwy 120
Tallapoosa, GA 30176

Main Building

- Remove old HVAC units and dispose of them properly.
- Replace PETAC unit with a mini split included in the 3 specified.
- Furnish and install new (24) W36HBDC09VP8XXE/W48HCDC09VPXXE Bard units.
- Furnish and install new (2) Bard units fuel type propane. These units will need a gas line installed.
- Furnish and install new (3) Mitsubishi mini splits adequate for heating and cooling the designated space.
- Furnish and install new (5) Trane model #YSC120H4RLA0000/YSH180G4RLC0000/YSH240G4RLC0000/YSH300G4RLC0000 RTU'S.
- Furnish and install new curb adapters.
- Furnish and install new condensate drain lines.
- Furnish and install new thermostats (Honeywell TH8321WF1001/U).
- Furnish and install new exhaust fans for ventilating restrooms and other code required spaces.
- Reconnect electrical and gas to units. (Please see drawings for clarification)
- Testing and balance of all units.
- Clean up the work area.

Freshman Academy

- Remove old HVAC units and dispose of them properly.

- Furnish and install new (18) W36HBDC09VP8XXE/W48HCDC09VPXXE Bard units.
- Furnish and install new (3) Mitsubishi mini splits adequate for heating and cooling the designated space.
- Furnish and install new condensate drain lines.
- Furnish and install new thermostats (Honeywell TH8321WF1001/U).
- Furnish and install new exhaust fans for ventilating restrooms and other code required spaces.
- Reconnect electrical and gas to units.
- Testing and balance of all units.
- Clean up the work area.

JROTC

- Remove old HVAC units and dispose of them properly.
- Furnish and install new (2) W36HBDC09VP8XXE Bard unit.
- Furnish and install new (2) Mitsubishi mini splits adequate for heating and cooling the designated space.
- Furnish and install new (1) 4 ton RTU WSC048H4RGA072R.
- Furnish and install new condensate drain lines.
- Furnish and install new thermostats (Honeywell TH8321WF1001/U).
- Furnish and install new exhaust fans for ventilating restrooms and other code required spaces.
- Reconnect electrical and gas to units.
- Testing and balance of all units.
- Clean up the work area.

Fine Arts Center

- Remove old HVAC units and dispose of them properly.
- Furnish and install new (2) Trane model #YSH180G4RLC0000.
- Furnish and install new (3) Mitsubishi mini splits adequate for heating and cooling the designated space.
- Furnish and install new (2) Unit heaters GLPD015ADG10000.
- Furnish and install new Trane split systems (3) S8X1D120M5PSCA/4TXCC007DS3HCA/4TTA4060A4000A.
- Furnish and install new (2) 4TTA4036A4000A (2) 4TTA4042A4000A (2) 4TTA4048A4000A.
- Furnish and install new curb adapters.
- Furnish and install new condensate drain lines.
- Furnish and install new thermostats (Honeywell TH8321WF1001/U).
- Furnish and install new exhaust fans for ventilating restrooms and other code required spaces.
- Reconnect electrical and gas to units.
- Testing and balance of all units.
- Clean up the work area.

CTAE

- Remove old HVAC units and dispose of them properly.
- Furnish and install new (1) Trane model #WSC090H4R0A0000 RTU.
- Furnish and install new curb adapters.
- Furnish and install new condensate drain lines.
- Furnish and install new thermostats (Honeywell TH8321WF1001/U).

- Furnish and install new exhaust fans for ventilating restrooms and other code required spaces.
- Reconnect electrical and gas to units.
- Testing and balance of all units.
- Clean up the work area.

Field House

- Remove old HVAC units and dispose of them properly.
- Furnish & install one (1) new Trane model # WSD240E4R0D0000 20-ton RTU.
- Furnish and install new curb adapters.
- Furnish and install new condensate drain lines.
- Furnish and install new thermostats (Honeywell TH8321WF1001/U).
- Furnish and install new exhaust fans for ventilating restrooms and other code required spaces.
- Reconnect electrical and gas to units.
- Testing and balance of all units.
- Clean up the work area.